

Regency Road to Pym Street Project

WORKS NOTIFICATION

September 2020



Construction of the Regency Road overpass, motorway, road infrastructure and landscaping

The Regency Road to Pym Street (R2P) Project has commenced construction of the Regency Road overpass and associated infrastructure including gantries, light poles, and communication cabinets that will be installed along the roadway. Landscaping will continue across the site where possible.

Where will the works be located and how long will the works take?

Works will occur along the North-South Motorway, Regency Road, South Road and at the Polonia Reserve compound.

What type of works are happening?

Regency Road overpass

Most of the Regency Road overpass will be assembled 'off site' at the Polonia Reserve compound.

While the bridge spans are being constructed off site, the on and off ramps and structures that support the bridge spans will be constructed at the South Road intersection with Regency Road.

Piling works for the overpass abutments and piers (structures that will support the bridge spans) and earthworks to construct the overpass ramps are underway at the intersection. The installation of the precast concrete wall panels commenced from the end of August 2020.

From mid-September 2020, girder segments (the support beams) for the bridge central spans will be delivered to the Polonia Reserve compound. The 12 girder segments are fabricated locally by South Australian Company Bowhill Engineering and will be transported and lifted onto the temporary support structures to enable the start of overpass assembly works.

For more information on piling works and the Regency Road overpass, view the fact sheets on our website: <https://r2palliance.com.au/resources/publications>.

Road infrastructure and motorway construction

Twenty-one gantries to support Variable Message Signs (VMS), Lane Use Management Systems and Closed-Circuit television (CCTV) (video security surveillance) are being installed along the North-South Motorway, South Road and Regency Road.

Piling works for gantry footings commenced in June 2020, and will continue until late October 2020. Following this, gantries will start to be installed, taking several months to complete, weather permitting.

Over the coming months, underground cables and light poles will continue to be installed for road lighting along the North-South Motorway, South Road and Regency Road. Twenty-one

CONTACT



1300 110 906



www.r2palliance.com.au



info@r2palliance.com.au



Australian Government

BUILDING OUR FUTURE



Government
of South Australia

Department for Infrastructure
and Transport

Regency Road to Pym Street Project

WORKS NOTIFICATION

September 2020



communication cabinets will also be installed alongside the roadway, verges and footpaths.

Motorway construction in September 2020 will focus on the removal of existing pavements and kerbing, and pavement construction works will be undertaken to build the road for placement of asphalt over the next several months.

Landscaping

Landscaping commenced in July 2020, and will continue until mid-2021. Works include the construction of pathways, compacted gravel verges, detention basins, and plantings. Landscaping plans will be available soon on the project website.

Work hours and traffic management

Most works will be undertaken during the day, between 6am and 6pm, Monday to Saturday. Where significant lane and speed restrictions are required, works will be undertaken at night, between 6pm and 6am, Sunday to Thursday. There will be no night works on Friday or Saturday nights. Noise impacts will be minimised as much as practically possible, however some noise will be unavoidable. Over the coming months, concrete pours for the overpass will be undertaken early in the morning, prior to 6am. Nearby residents will be notified.

Traffic management and signage will be in place to alert road users to any changed traffic conditions. Road users are asked to plan ahead and take extra care when workers are on site. Observe speed limits, lane restrictions and traffic controllers when travelling through the area.

SitePodium

Stay up-to-date with the project via the new SitePodium App, visit <https://r2palliance.com.au/resources/sitepodium-app> for details on how to download the App.

Community noticeboards

Two community noticeboards have been installed at Polonia Reserve, on the fence near the entrance gate on Essex Crescent, and in Hudson Avenue Reserve. The noticeboards are updated weekly with works notifications, fact sheets, latest news and construction images.

Questions?

If you have any questions or would like printed copies of any fact sheets, please phone the project team on **1300 110 906** or email: info@r2palliance.com.au.

CONTACT



1300 110 906



www.r2palliance.com.au



info@r2palliance.com.au



Australian Government

BUILDING OUR FUTURE



Government
of South Australia

Department for Infrastructure
and Transport